

# Why NewTechWood® with UltraShield?

v20200610 AUS

# Outline

Historic Problems & The Solution	2-5
Why All Weather System • Capped Composite • Engineered Design System	6-15
Installation	16-21



# **UltraShield**<sup>®</sup>

### Why insist to cap completely around ?





# To make the board capped 360 degree around :

- It will give the board maximum protection and STOP all the first generation product problems and also the non-360 capped board problems such as :
  a) Cupping , b) Cracking and c) Swelling
- 2. It requires more sophistication in technology, advanced skills and knowledge in mould design BUT NewTechWood insists to make all UltraShield® boards with 360 degree fully capped composite products, including the tiny area of the groove.



### Because this is the only way to give ULTRA protection



### **1.** Five types of PE Composite Wood in the Current Market

Based on PE composite wood market, they can be divided into capped and non capped composite wood. Five different types of composite wood can be identified as follows.













Picture shown: Type A: 360 degree completely capped, including groove



### 2. Potential problems for non capped composite wood product

F

Π



No Skin?

Non capped, known as first generation

0 😮

First generation (non capped) composite wood has no cap layer to protect the core.

Cap layer contains wood powder

Some capped composite wood products contain wood powder in their cap layer, which means that wood powder is still exposed to the elements and can still succumb to the problems of the first generation.



# **Potential Problems**

### 1. Crumbling

- 2. Colour Fading
- 3. Fungus & Mould & Mildew
- 4. Cracking
- 5. Scratching
- 6. Staining

Without a capped layer to protect the core, the wood fibre is exposed to the surface and damaged by various harsh weather conditions, UV, moisture, bacteria, fungus and mould.

Not only the colour will be faded out, the structure and composition will be degraded or even destroyed.



# 1. Crumbling

• When the first generation composite boards are exposed to the UV and water, it begins to decompose. This is due to an improper amount of bonding agent and antioxidant added to the composite material.

Ultimately, the wood fibre absorbs moisture with UV together which causes composite decking to decay, crumble, deteriorate and rot.













and the second second research from the second s and the second second second at the the second se and the second of the second and the second and the second and the second the second the second and n andre and a stand of the second of the sec and and an instant and side of for de lance my parties tomate and and a start to a discover and a start of the start of and and the liter of a second and with the second as the second and the state of the state of the section of the state of the and and a stand of the stand of and the state and the second share is a second at an and a second and the set it is as a and the stand of the stand of a standing of the stand of the stand where the second is a second of the second have the second where the second sec I what we will and and my and water what when it is the water af march a provide the contract and a shak a wall the second of the second a second the state of the terminant and the state of the state of

# 2. Colour Fading

• The reason for colour fading comes from the wood fibre content. Wood naturally fades if not protected. Most of the time manufacturers brush their boards which damages the plastic, allowing the wood fibres to be exposed to the surface. Inconsistent fading occurs due to the manufacturer's inability to control the consistency of the colourant and raw materials being added.

Colour difference - many decks were faded with uneven colour resulting in some boards being lighter and others appearing darker.





# 3. Fungus, Mould, Mildew

• Fungus, mould, and mildew problems are usually found in climates with extreme humidity or climate change. When not protected by a sealant or treated, the wood fibres are attacked when they are exposed to the elements.

Many people have tried to use deck cleaners to clean off the mould, but once the layer that is sealed/protected by the cleaner wears off, the mould will just attack the other layers below.





# 4. Cracking

• Many manufacturers add calcium / filler to their product to enhance the stiffness of the board, but it makes the board more brittle. Therefore, when installers try to drill into the board there is a potential that it might crack.





# 5. Scratching

• The first generation composite's scratch resistance is very poor and this is due in part because of the wood fibres. Wood fibres inherently have a low scratch resistance and when the manufacturer brushes/sands the board, it creates a coarse effect on the surface, allowing for even less scratch resistance.





# 6. Staining

• Without any cap protection, any stains will be absorbed by the wood fibre or penetrate in between the wood fibre and polymer directly and permanently.







### Half Shield?

Some capped composite wood is only half capped; this solves some problems, but other problems occur.

Half capped composite wood



• Capping the top half of the board does provide higher stain, scratch, and UV resistance, however, the underside and grooves of the board are exposed to the elements and that creates dry and wet effects on the top and bottom.



# 7. Swelling & Cupping





- The shield uses a virgin engineering grade polymer that has an extremely low water absorption rate. The shield on a half capped board is only protecting the top, meaning that the bottom is still exposed in a similar fashion as the first generation composite.
- Therefore, on a very humid day, the bottom will continually absorb moisture and the top will be almost completely dry. This creates a cupping/ twisting effect on the board similar to real wood. The force of this effect can be so strong that it actually tears/splits the core in half as shown below.









# Uninstalled deck boards

# Cracking

# 8. Cracking in the cap layer

• As the inner core continues to gain moisture, the force could get so strong that it tears the cap layer as well.







# Cracking



### Shield cut?

Some manufacturers extrude a fully capped board and then cut the grooves on both sides to cut costs. (One mould to do two profiles, grooved and ungrooved). The other reason could be that technically, they are not as advanced in mould designing.

B

Groove was cut out, not completely capped



• A board with an uncapped groove still allows moisture to be absorbed into the core through the entire length of the board. Therefore, there is a potential for swelling, cupping, and cracking to exist over time.





360 degree capped shield!



Capping 360 degrees provides complete protection all around the board and even in the groove of the board. This is the only way to completely protect the board from UV, water, insects, and any other mould/mildew from attacking the core.





Note: The core is still susceptible to the outside elements, so it is recommended to either use a sealant or end caps to cover up any ends that are not protected.



# UltraShield® Advanced Capped Composite Material

has a strong and durable polymer shield capping the core 360 degrees.

- The Core is made of wood fibre, PE polymer and additives.
- The Shield is made of special engineering grade polymer and additives with extremely low water penetration.



The Shield prevents moisture penetration inside the core, resisting problems like:

- $\times$  Rot
- × Split & Crack
- × Fungus & mould\*\*

→The Shield is durable and gives a longer life span so that you can enjoy your time on your deck with minimal maintenance.

\*\* Note: mould can still occur on the board through outside substances such as food, tannins, etc. that are left on the surface of the board if not cleaned within a reasonable amount of time. Please read the care and cleaning guide to get more information.

The Shield gives maximum protection against:

√ Staining √ Fading √ Mould / Mildew √ Scratches



→ The shield maintains a pleasant look for years to come and needs no painting, sanding, or oiling of any kind.

# 3. Focus in testing capped composite wood

3.1 Stain Test

- 3.2 Scratch Test
- 3.3 Abrasion Test
- 3.4 UV Test
- 3.5 Boiling Test
- 3.6 Ash Content Test



# 3.1 Stain Test





# UltraShield<sup>®</sup>





### Wipe off half of the ink



















**UltraShield<sup>®</sup>:** No penetration through the top layer and no stain left







# 3.2 Scratch Test

- Use 1 mm needle
- Test scratch damage under 8N-20N pressure
- Test Standard: FLTM BO 162-01



# Original



# UltraShield<sup>®</sup>







UltraShield<sup>®</sup> 20N: No obvious mark





# 3.3 Abrasion Test

- Testing: 750g Weight,60 turns/min, 1000 turns
- Test Standard: ASTM D4060



### Original







#### Scratch mark and the wore off powder weight after test







# 3.4 UV Test

• QUV chamber test up to 3000 hours. Observation & record every 500 hours



UltraShield<sup>®</sup> 500 hrs: Delta E: 0.65 - 1.25

UltraShield<sup>®</sup> 1000 hrs: Delta E: 0.92 - 1.41





UltraShield<sup>®</sup> 1500 hrs: Delta E: 1.45 - 1.63

### UltraShield<sup>®</sup> 2000 hrs: Delta E: 2.55 – 3.54



Original Sample Tested Sample	Original Sample Tested Sample	Original Sample Tested Sample	Original Sample Tested Sample		
Model: US01. After 2500 h test, Gray Scale=3-4, △E*=2.72	Model: US02. After 2500 h test, Gray Scale=3, △ E*=3.63	Model: US02, Part showed some color change. There was no other visible surface damage. After 3000 hours test. AE*=3.75 Grav Scale 3.	Model: UH02, Part showed some color change. There was no other visible surface damage. After 3000 hours test AE*=3.56 Gray Scale 3.		
Original Sample	Original Sample Tested Sample	Original Sample Model: UH07, Part showed some color change.	Original Sample Model: US01, Part showed some color change.		
Model: UH02.   Model: UH07.     After 2500 h test, Gray Scale=3, △ E*=3.31   After 2500 h test, Gray Scale=3, △ E*=3.		There was no other visible surface damage. After 3000 hours test, $\Delta E^*=3.64$ Gray Scale 3.	There was no other visible surface damage. After 2500 hours test, $\Delta E^*=2.72$ Gray Scale 3-4.		

UltraShield<sup>®</sup> 2500 hrs: Delta E: 2.72 - 3.63 UltraShield<sup>®</sup> 3000 hrs: Delta E: 2.72 - 3.75





Tested in a QUV chamber for 3000 hours, no visible colour change can be observed (Delta E <4.0)



# 3.5 Boiling Test

- 1. Put the test samples in the container (the water level needs to be over the samples by at least 5mm or more
- 2. Turn on the heating plate to 100℃ and observe every 2 hours
- 3. Samples need to be taken out every day and the duration should be recorded. The duration is recorded after the temperature of the hot plate reaches 100℃
- 4. Repeat procedure 1-3 on the second day.



• Boil the board up to 80 hours or more.











80hr 90hr

Pictures above show UltraShield<sup>®</sup> after a 90 hrs boiling test. The results show no separation between the cap layer and the core, no damage and no cracking.







Some other Brands of fully capped composite wood shown cracking in both the capped layer and the core after 15 hrs boiling test:

The shield shown 2 cracks, 30mm The core shown 2 cracks, 3-5mm







Some other Brand of fully capped composite wood shown separation after 41 hrs boiling test: Picture shown separation, 2-3mm







Some other Brands of groove cut capped composite wood shown separation after 18.5 hrs boiling test: Picture shown 3 spots of separation at the grooves, 2-5mm And cracking in the core 2-4mm







107.5 hrs boiling test.







# **3.6 Ash Content Test**

1. Measure the weight of the material.

- 2. Put the material into the Muffle furnace for 6hours at 600℃±25℃
- 3. Measure the ash content and the weight of the material after it cools down.

Test Standard: GB/T 9345.1—2008/ISO 3451-1:1997



• Percentage of the ash content is calculated by the formula

$rac{m_1}{m_0} imes 100$	m0Sample weight (g)
	m1Ash weight (g)

No.	Conventional Ash Content (%)	UltraShield Ash Content (%)
1	10.10	3.19
2	10.58	3.43
3	10.84	3.26
4	10.03	3.44
5	10.20	3.45
6	10.77	3.18
Average	10.42	3.33

The main substance in ash content is fillers (inorganic substances). The higher the ash content means that there are more fillers which makes the product easier to crack.



# 4. The colour and surface treatment

Besides the durability, the range of available colours is a very important element for the growth of capped composite.

NewTechWood UltraShield currently has 22 colours and will continue to develop more colours.



# UltraShield® Naturale Colours

Oak	Teak	lpe	Mahogany	Walnut	Redwood	Merbau	Smoke White	Antique	Stone Gray	Mirage Gray
(OK)	(Tk)	(IP)	(MAH)	(WN)	(RW)	(MB)	(SW)	(AT)	(ST)	(MG)
Silver Gray	Light Gray	Charcoal	Sand	Cedar	Maple	Red Cedar	Swedish Red	Orange	Sky Blue	Spring Green
(SI)	(LG)	(CH)	(SD)	(CE)	(MP)	(RCE)	(SR)	(OR)	(SB)	(SG)



# UltraShield<sup>®</sup> Naturale<sup>®</sup> Patterns













For more information, please visit www.newtechwood.com.au 73